

Bruhat Bangalore Mahanagara Palike
Executive Engineer Dasarahalli Division

**Name of Work: Improvements and Asphaltting to Saptagiri College Main and adjacent
Cross roads in ward No 12, Shettyhalli Sub Division**

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Civil Work								
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications 10km lead= $57+2.0 \times 1.28 \times 10 = 82.60$								
	CC Drain								
	Sapthagiri College Road	1	198.00	1.20	0.90	213.84			
		1	69.00	1.50	1.20	124.20			
	RHS 2nd Crs Sapthagiri Main	1	97.00	1.20	0.90	104.76			
	RHS 3rd Crs Sapthagiri Main	2	120.00	1.20	0.90	259.20			
	RHS 4th Crss frm Sapthagiri Main	2	120.00	1.20	0.90	259.20			
	Cross Road-1 frm 4th Cross	2	33.50	1.20	0.90	72.36			
	Cross Road-2 frm 4th Cross	2	32.50	1.20	0.90	70.20			
	LHS 4th Crss frm Sapthagiri Main	1	230.00	1.20	0.90	248.40			
						1352.16	Cum	220.40	298016.06
2	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)								
	CC Drain								
	Sapthagiri College Road	1	198.00	1.20	0.15	35.64			
		1	69.00	1.50	0.15	15.53			
	RHS 2nd Crs Sapthagiri Main	1	97.00	1.20	0.15	17.46			
	RHS 3rd Crs Sapthagiri Main	2	120.00	1.20	0.15	43.20			
	RHS 4th Crss frm Sapthagiri Main	2	120.00	1.20	0.15	43.20			
	Cross Road-1 frm 4th Cross	2	33.50	1.20	0.15	12.06			
	Cross Road-2 frm 4th Cross	2	32.50	1.20	0.15	11.70			
	LHS 4th Crss frm Sapthagiri Main	1	230.00	1.20	0.15	41.40			
						220.19	Cum	5421.90	1193821.05

Sl	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications do- Wall & bottom thickness 15cm (I No-37.59.2,P No-271)								
	CC Drain								
	Sapthagiri College Road	1	198.00	0.90	0.15	26.73			
		1	69.00	1.20	0.15	12.42			
	RHS 2nd Crs Sapthagiri Main	1	97.00	0.90	0.15	13.10			
	RHS 3rd Crs Sapthagiri Main	2	120.00	0.90	0.15	32.40			
	RHS 4th Crss frm Sapthagiri Main	2	120.00	0.90	0.15	32.40			
	Cross Road-1 frm 4th Cross	2	33.50	0.90	0.15	9.05			
	Cross Road-2 frm 4th Cross	2	32.50	0.90	0.15	8.78			
	LHS 4th Crss frm Sapthagiri Main	1	230.00	0.90	0.15	31.05			
	CC Drain Wall								
	Sapthagiri College Road	2	198.00	0.15	0.60	35.64			
		2	69.00	0.15	1.20	24.84			
	RHS 2nd Crs Sapthagiri Main	2	97.00	0.15	0.60	17.46			
	RHS 3rd Crs Sapthagiri Main	4	120.00	0.15	0.60	43.20			
	RHS 4th Crss frm Sapthagiri Main	4	120.00	0.15	0.60	43.20			
	Cross Road-1 frm 4th Cross	4	33.50	0.15	0.60	12.06			
	Cross Road-2 frm 4th Cross	4	32.50	0.15	0.60	11.70			
	LHS 4th Crss frm Sapthagiri Main	2	230.00	0.15	0.60	41.40			
						395.42	Cum	7070.20	2795663.13
4	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. Specificatio(I No-28.8.2,P No-229)								
	Consider 75kg/Cum	1	395.42	75.00		29656.13			
						29.66	Tn	72326.98	2144937.96
5	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)								

SI	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	CC Drain								
	Sapthagiri College Road	1	198.00	0.90		178.20			
		1	69.00	1.20		82.80			
	RHS 2nd Crs Sapthagiri Main	1	97.00	0.90		87.30			
	RHS 3rd Crs Sapthagiri Main	2	120.00	0.90		216.00			
	RHS 4th Crss frm Sapthagiri Main	2	120.00	0.90		216.00			
	Cross Road-1 frm 4th Cross	2	33.50	0.90		60.30			
	Cross Road-2 frm 4th Cross	2	32.50	0.90		58.50			
	LHS 4th Crss frm Sapthagiri Main	1	230.00	0.90		207.00			
						1106.10	Sqm	2208.00	2442268.80
6	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 10km lead= (I No-19.14,P No-143)								
	Sapthagiri College Road								
	Ch:0.00m to 843.00m	1	843.00	6.75	0.250	1422.56			
						1422.56	Cum	69.06	98,242.17
7	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications (I No-19.64,P No-147)								
	Sapthagiri College Road								
	Ch:0.00m to 843.00m	1	843.00	6.75		5690.25			
						5690.25	Sqm	6.36	36,189.99
8	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications Clause 401 of MORTH V Revision.(I No-20.5,P No-153)								
	Sapthagiri College Road								
	Ch:0.00m to 843.00m	1	843.00	6.75	0.15	853.54			
						853.54	Cum	1994.92	1702739.03
9	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	Sapthagiri College Road								
	Ch:0.00m to 843.00m	1	843.00	6.75	0.23	1280.31			
						1280.31	Cum	2001.28	2562251.29

[illegible]

SI	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
		199984	15.99						
		1584	01						
	Sub Total								19996286.11
	Utility Shifting, Miscellaneous and Rounding off								3,713.89
	GRAND TOTAL								20000000.00

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR, Bangalore circle for year 2016-2017. and Data Rates




Assistant Engineer
Ward No-12
BBMP Bangalore

Asst. Executive Engineer,
Shettyhalli Sub Division
BBMP Bangalore

Executive Engineer,
Dasarahalli Division
BBMP Bangalore

ನಂ. BBMP/EE/AS/173 ದಿನಾಂಕ : 20.02.2019
ದಾ. 200.00 Lakhs/- (Rs Two Hundred Lakhs only)
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಧಾರವಾಗಿ ಸಂಪೂರ್ಣವಾಗಿ ನೀಡಿದ
ಶಾಖಾಪಾಲಕ ಅಧಿಕಾರಿಗಳು
ದಾಖಲೆ, ಖಾತೆ, ಅನುಮತಿ.

ನಂ. E/02/TS/19/18-19 ದಿನಾಂಕ : 22/02/2019
ದಾ. 200.00 Lakhs/- (Rs Two Hundred Lakhs only)
ಈ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು ಮುಖ್ಯ ಅಭಿಯಂತರರು
29.02.2019
ದಾಖಲೆ, ಖಾತೆ, ಅನುಮತಿ.



ಸಹಾಯಕ ಕಾರ್ಯದರ್ಶಿಗಳು ಅಭಿಯಂತರರು
ಶಿಕ್ಷಣ ಉಪವಿಭಾಗ, ದಾಸರಹಳ್ಳಿ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಕಾರ್ಯದರ್ಶಿ, ರಸ್ತೆ ವಿಭಾಗ, ಬೆಂಗಳೂರು

Map data ©2019 India Terms Send feedback
KALASH EXCLUSIVE
Babanna

Dwg Title:
PLAN

PROJECT
Improvements and Asphaltting to Saptagiri College Main and adjacent Cross roads in ward No 12, Shettyhalli Sub Division

LIENT:
URUHAT BANGALORE MAHANAGARA PALIKE

